Name of Range	Name of Forest	Length of the line	Rate per mile	Amount
		Ml. F.	Rs. a. p.	Rs. a. p.
Chitaldrug ..	Jogimatti	49 0		
	Rangayyandurga	59 0		
	Do (Block line) ..	7 0		
	Anabur (Exterior)	30 4		
	Do (Block line)	6 0		
	Jagalur block (Exterior)	11 2		
	Guheswaragudda do	10 0		
Hiriyur Range ..	Lakkihalli	31 0		
	Marikanive	34 4		
	Swarnamukhi	26 2		
	Kudurekanive	40 6		
	Gowdanhalli	15 0		

A. V. KESAVIENGAR,
District Forest Officer.

ENGINEERING DEPARTMENT

BUILDINGS DIVISION, BANGALORE.

Dated 4th September 1937.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Buildings Division, up to 24th September 1937, up to 2-30 P.M., for constructing a Manufacturing Hall with a Cellar in Porcelain Factory, Bangalore. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of January 1938.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Buildings Division between the hours of 11 A.M. to 5 P.M.

3. Tender should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 1,000 (one thousand) in cash or Government Promissory Notes as earnest money, and be superscribed "Tender for Constructing a Manufacturing Hall with a Cellar in Porcelain Factory, Bangalore" in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

Abstract estimate for constructing a Manufacturing Hall with a Cellar in Porcelain Factory, Bangalore.

No.	Items of work	Per	Rate	Quantity	Rate to be quoted
			Rs. a. p.		
1	Earthwork excavation for foundation	C.yd.	0 3 6	225	
2	Granite jelly concrete in lime mortar	C.ft.	0 3 6	1,060	
3	Size stone in lime mortar	,,	0 4 6	4,303	
4	Burnt brick in mud	,,	0 3 6	3,003	
5	Burnt stone slab 6" thick exposed portions 1 line dressed and fixed in mortar for basement	S.ft.	0 5 0	573	
6	Burnt stone slabs 5" to 6" thick roughly dressed and fixed	,,	0 4 6	659	
7	Do 2 line dressed and fixed	,,	0 6 6	45	
8	Cement jelly concrete	C.ft.	0 12 0	990	
9	Teakwood doors with battened shutters and iron fittings, etc., complete	S.ft.	1 6 0	108	
10	Teakwood windows ¾" iron bars and iron fittings, etc., complete	S.ft.	1 8 0	480	
11	Burnt brick in lime mortar	C.ft.	0 4 6	1,088	
12	Tatas tested steel girders and stanctions	Cwts.	15 0 0	199	
13	Mild steel truss of 20' span at 10' apart including hoisting and fixing	,,	16 0 0	88	
14	Angle iron brackets to join girders and stanctions with drilling holes, bolts, nuts, etc., complete	Each	3 8 0	22	
15	Flat iron brackets for fixing purlins with stanctions including drilling holes, bolts and nuts etc., complete	,,	2 8 0	22	
16	Teakwood wrought and put up with wood oiling	C.ft.	5 0 0	546·73	
17	Roofing with 1st Class Mangalore pattern tiles over teak reepers 2"×1" with wood oiling to reepers	Sqr.	23 0 0	79·95	
18	Mangalore Ridge tiles set in mortar	R.ft.	0 7 0	123	
19	Joining truss with stanctions with angle iron, bed plate, etc., complete	Each	2 8 0	22	
20	Removing and refixing old roof with rafters, etc., complete	Sqr.	4 0 0	1·28	
21	Dismantling old wall alternate courses brick or stone and rebuilding complete	C.ft.	0 5 0	45	
22	Flooring with 1½" of 1 : 2 : 4 cement concrete over 3" of 1 : 4 lime concrete with nice finish at top	Sqr.	20 0 0	51·60	
23	Lime mortar plastering 2 coats	,,	3 0 0	63·03	
24	White and color washing 2 coats	,,	0 4 6	63·03	
25	Lac Factory green painting	,,	4 0 0	20·98	
26	Teakwood eave board 9" width ¾" thick plain	R.ft.	0 7 0	308	
27	Removing and refixing old eave board	,,	0 1 0	64	
28	Cement pointing to basement	Sqr.	2 8 0	8·67	
29	Teakwood finals	No.	0 8 0	1	
30	Teakwood pendents	,,	0 4 0	4	
31	Burnt brick in mortar band	R.ft.	0 4 0	64	
32	Earthwork filling basement lead for earth ½ a furlong including carting and consolidating	C.yd.	0 6 0	349	
33	Glazed pannel shutters in teak frame fixed with bolts and nuts, etc., complete	S.ft.	1 0 0	720	
	Cellar Room.				
1	Earthwork excavation for foundation for under ground cellar and the walls alround cellar in hard soil	C.yd.	0 6 0	223	
2	Granite jelly concrete in lime mortar	C.ft.	0 3 6	487	

No.	Items of work	Per	Rate	Quantity	Rate to be quoted
			Rs. a. p.		
3	Size stone in lime mortar in foundation and superstructure	Cft.	0 4 6	2,490	
4	Burnt stone slabs 6″ thick 2 line dressed and fixed for steps	,,	0 6 6	49	
5	Burnt stone slabs 5″ to 6″ thick dressed and fixed for lintels and sills and bed slab of girders	Sft.	0 4 6	38	
6	Teakwood door with battened shutters, iron fittings, etc., complete	,,	1 6 0	36	
7	Supplying and fixing Tatas Tested R. S. joists 12″×5″, etc., complete	Cwt.	15 0 0	9.7	
8	Reinforced cement concrete slab roofing with 1 : 2 : 4 as per standard specification 4½″ thick with ⅜″ rods fitted 4½″ apart with 3″ of surki concrete and 2 courses of flat tiles laid in 1 : 2 lime mortar finished with ½″ of lime mortar plaster at top and smooth lime ceiling mortar below	Sqr.	85 0 0	5.00	
9	Cement pointing	,,	2 8 0	8.10	
10	Lac Factory green painting	,,	4 0 0	1.00	
11	Flooring with 1½″ of 1 : 2 : 4 cement concrete over 3″ of 1 : 4 lime concrete with nice finish at top	,,	20 0 0	4.50	
12	Providing hand railing with cast iron pipes and up rights for the opening for steps at top ..	..	L. S.	Rs.	

B. R. GARUDACHAR,
Executive Engineer.

WATER-SUPPLY DIVISION.

Abstract Notification dated 1st September 1937.

The attention of the public is invited to notification regarding lapsed Deposits of the late Chamarajsagar Division, published on pages 1473-1475, Part VI of the *Mysore Gazette*, dated 9th September 1937.

V. GANESHA IYER,
Executive Engineer.

MYSORE DIVISION.

Notification dated 8th September 1937.

Sealed tenders will be received at the Office of the Executive Engineer, Mysore Division, up to 12 NOON on 27th September 1937, for improving Chamasagara Anicut, Chamarajnagar Taluk.

2. Tenders in the prescribed form obtainable from the Office of the Executive Engineer, Mysore Division, should be addressed to the Executive Engineer, Mysore Division, in a sealed cover and superscribed as "Tender for Improving Chamasagara Anicut." The name of the tenderer should also be superscribed on the top of the cover.

3. Each tender must be accompanied by a deposit of Rs. 490 (in words) Rupees four hundred and ninety and deposited in Government Treasury under 17(a) Public Works Deposits on Government Promissory notes duly endorsed at face value or market value whichever is less, as earnest money. The earnest money of the successful tenderer will be retained as security deposit for due fulfilment of the contract. Such a deposit in cash will not carry any interest.

4. The tenders will be opened in the presence of such tenderers who wish to be present on 28th September 1937 at Mysore. The final acceptance of the tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender, or to assign any reason whatever for the rejection of any.

5. The name of the successful tenderer will be posted on the Notice Board in the Executive Engineer's Office, in due course. Within eight days of the acceptance of the tender, the successful tenderer will be required to execute an agreement in the departmental schedule contract form, for the due fulfilment of the contract, and for the execution of all items of work in accordance with the Bombay specifications (1931).

6. Failure to comply with the condition 5 above or to agree to carry out the work in accordance with the specifications and agreements in force, will entail forfeiture of the earnest money.

7. The earnest money of rejected tenders will be returned on submission of the receipt originally granted, along with an application to the Executive Engineer.

8. Copies of contract documents, schedules and drawings may be seen at any time at the Executive Engineer's Office, Mysore, on all working days between 11 A.M. and 5 P.M. and may be obtained from that officer on payment of Rs. nil.

9. Specific rates should be given for each item in the schedule accompanying the tender and the rates should be in rupees, annas and pies and expressed in words and figures. Tenders offering a percentage reduction on the estimate amount will be rejected.

10. Any rates or lumpsum amounts for the items not called for, if tendered by the tenderer, will not be taken notice of. The rates for such items may be entered in a separate schedule with date and reasons for the same.

11. No alterations which are made by the tenderers in the tender form in the nomenclature of the items of work will be recognised and if corrections are made the tenders are liable to rejection.

12. There should be no alterations or erasures in the tenders in the rates of items and any corrections made in the rates should be attested to, and the number of corrections, if any, in each page noted at the foot of the same by the tenderer.

13. No reference should be made to the Public Works Department schedule of rates.

14. In the event of the tender being submitted by a Firm, it must be signed separately and severally by each member thereof, or in the event of absence of any partner, it must be signed on his behalf by a person holding power-of-attorney, authorising him to do so.

15. When once the rates tendered have been accepted, they will not be revised under any circumstances. In regard to items of work not tendered, the rates for the same will be calculated by the Executive Engineer on the basis of current rates for materials and labour with a contractor's profit of 5 per cent as may be approved by the Superintending Engineer. This shall be final and legally binding on the tenderer.

16. The quantities given in the schedule are only approximate and the drawings shown to the contractor are only tentative and are liable to alterations, omissions, deductions, or additions at the discretion of the Executive Engineer or his representative. The tendered rates will hold good for any quantity, whether higher or lower than those given in the enclosed schedule.

17. The works should be completed and handed over in a tidy condition to the Public Works Department by the end of December 1937, failing which, the Executive Engineer may, at his discretion, levy a penalty of Rs. 10 per day, which will ordinarily be calculated at 12 per cent per annum on the total outlay as liquidated damages for non-fulfilment of contract, and will be recovered from the Contractor's outstandings for the period exceeded by him beyond the time fixed and until the work is completed and handed over.

18. In all matters of disputes of any kind not specially provided for in the agreement or of rates, penalties, measurements, quality of work, etc., the decision of the Chief or the Superintending Engineer shall be final and legally binding.

19. No claim for damages, for delays caused by Officers of the Department in the execution of the work will be considered, whatever may be the reasons for such delays. Contractors should bear this in mind when tendering for the work. Extension of time due to delays caused by the departmental officers will however be considered on the merits of each case.

20. The contract should not be sublet.

21. All materials, tools and plant and machinery that will be supplied by the Executive Engineer, in the interest of the work shall be accepted by the tenderer at the rates fixed by the Executive Engineer. The tenderer will pay the hire on tools and plant and machinery as per rules from the date of taking over of such machinery, tools and plant from the Stores to the date of return thereto, the dates considered being, the dates of acknowledgments of the vouchers in each transaction.

22. The contractor should arrange for the payment of royalty and tolls.

Note (*A*).—The Contractor should at his own cost—

(1) Provide rods, stakes, ropes and labour required in setting out the works.
(2) Provide all necessary scaffolding, centering labour and appliances for hoisting.
(3) Provide mortar mills and sheds to keep materials under cover and also for workmen.
(4) Arrange for protecting work during inclement weather.

(5) Supply requisite temporary lights, water cisterns, water pumps and hoses, sieves, parahs, shoring, strutting and other requisite protective appliances during the progress of the work.

(6) Supply all water required for work and workmen and shall provide temporary latrines and drains.

(7) Clean away all dirt, rubbish, superfluous materials and debris as they accumulate.

(8) Provide arrangements for pumping and baling of water from excavations and foundations, wherever and whenever necessary with his own pumping apparatus including necessary leading drains, slump pits, etc.

(9) Afford facilities to any other parties employed upon the work by the P. W. D. so that their work may proceed during the progress of the contract, and allow such persons the use of ordinary scaffolding and ladders.

(10) The contractor is responsible for all accidents to workmen, etc., on the work and he must take precaution against all risk of accidents and if necessary provide for the same by insurance at the proper time.

Note (*B*).—It is the business of the contractor to make his own arrangements for quarries and supplies of materials.

Abstract estimate for Improving Chamasagara Anicut, Chamarajnagar Taluk.

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		Rs.
1	Earthwork excavation benching rock, etc., (Earthwork to be quoted by c.yds. and benching by s.ft.)	L. S.	..	..	50
2	(*a*) Burnt stone jelly concrete in surki mortar (1½ lime : 1 surki : 2 sand)	C.ft.	0 4 0	3,075	769
	(*b*) Alternately in cement mortar 1 : 5 : 10 ..	,,	0 6 0	3,075	1,153
3	(*a*) Size stone in surki mortar (1½ lime : 1 surki : 2 sand)	,,	0 5 6	4,745	1,631
	(*b*) Alternately in cement mortar 1 : 6 ..	,,	0 6 6	4,745	1,927
4	(*a*) Burnt stone slabs 9″ thick dressed and fixed in surki mortar	S.ft.	0 12 0	1,633	1,225
	(*b*) Do alternately in cement mortar 1 : 6	,,	0 13 0	1,633	1,327
5	(*a*) Do do 6″ do ..	,,	0 8 6	258	137
	(*b*) Do do alternately in cement mortar 1 : 6	,,	0 9 6	258	153
6	(*a*) Burnt stone jelly concrete 3″ thick with surki mortar 1½ lime : 1 surki : 2 sand and cement rendering	Sqr.	10 0 0	3·10	31
	(*b*) or alternately cement concrete 1 : 4 : 8 ..	,,	16 0 0	3·10	50
7	Cement pointing 1 : 3	,,	3 0 0	18·00	54
8	Rough stone work with jelly packing ..	C.yd.	2 0 0	116	232
9	Chisiling and providing bond stones in front of anicut to join new with the old work ..	Lump sum Rupees to be paid by s.ft.			50
10	Earthwork to bank and turfing, etc. .. (Earthwork to be quoted by c.yd. and turfing by sqrs.	L. S.	..	..	50
11	Marking gauge in cement and painting with the White lead and Japan in returns of the anicut with figures carved	L. S.	..	..	15
	Total ..				4,244

Notification dated 10th September 1937.

1. Sealed tenders will be received at the Office of the Executive Engineer, Mysore Division, up to 12 NOON on 27th September 1937, for Restoring Dadamuduki Gundakalkere (Minor Tank) Nagamangala Taluk.

2. Tenders in the prescribed form obtainable from the Office of the Executive Engineer, Mysore Division, should be addressed to the Executive Engineer, Mysore Division, in a sealed cover

and superscribed as "Tender for Restoring Dadamudike Gundakalkere." The name of the tenderer should also be superscribed on the top of the cover.

3. Each tender must be accompanied by a deposit of Rs. 1,000 (in words)Rupees one thousand deposited in Government Treasury under (a) P. W. Deposits of Government Promissory Notes is duly endorsed at face value or market value, whichever is less, as earnest money. The earnest money of the successful tenderer will be retained as security deposit for due fulfilment of the contract. Such a deposit in cash will not carry any interest.

4. The tenders will be opened in the presence of such tenderers who wish to be present on 8th September 1937 at Mysore. The final acceptance of the tender will rest with the Engineer, who does not bind himself to accept the lowest or any tender, or to assign any reason whatever for the rejection of any.

5. The name of the successful tenderer will be posted on the Notice Board in the Executive Engineer's Office in due course. Within eight days of the acceptance of the tender, the successful tenderer will be required to execute an agreement in the departmental schedule contract form, for the due fulfilment of the contract and for the execution of all items of work in accordance with the Bombay specifications (1931).

6. Failure to comply with the condition 5 above or to agree to carry out the work in accordance with the specifications and agreements in force will entail forfeiture of the earnest money.

7. The earnest money of rejected tenders will be returned on submission of the receipt originally granted, along with an application to the Executive Engineer.

8. Copies of contract documents, schedules and drawings may be seen at any time at the Executive Engineer's Office, Mysore, on all working days, between 11 A.M. and 5 P.M. and may be obtained from that officer on payment of Rs. nil.

9. Specific rates should be given for each item in the schedule accompanying the tender and the rates should be in rupees, annas and pies and expressed in words and figures. Tenders offering a percentage reduction on the estimate amount will be rejected.

10. Any rates or lumpsum amounts for the items not called for, if tendered by the tenderer, will not be taken notice of. The rates for such items may be entered in a separate schedule with date and reasons for the same.

11. No alterations which are made by the tenderers in the tender form in the nomenclature of the items of work will be recognised and if corrections are made, the tenders are liable to rejection.

12. There should be no alterations or erasures in the tenders in the rates of items and any corrections made in the rates should be attested to and the number of corrections, if any, in each page noted at the foot of the same by the tenderer.

13. No reference should be made to the Public Works Department schedule of rates.

14. In the event of the tender being submitted by a firm, it must be signed separately and severally by each member thereof, or in the event of absence of any partner, it must be signed on his behalf by a person holding power-of-attorney authorising him to do so.

15. When once the rates tendered have been accepted, they will not be revised under any circumstances. In regard to items of work not tendered, the rates for the same will be calculated by the Executive Engineer, on the basis of current rates for materials and labour with a contractor's profit of 5 per cent as may be approved by the Superintending Engineer. This shall be final and legally binding on the tenderer.

16. The quantities given in the schedule are only approximate and the drawings shown to the contractor are only tentative and are liable to alterations, omissions, deductions, or additions, at the discretion of the Executive Engineer or his representative. The tendered rates will hold good for any quantity, whether higher or lower than those given in the enclosed schedule.

17. The work should be completed and handed over in a tidy condition to the Public Works Department by the end of December 1938, failing which the Executive Engineer may, at his discretion, levy a penalty of Rs. 20 per day, which will ordinarily be calculated at 12 per cent per annum on the total outlay as liquidated damages for non-fulfilment of contract, and will be recovered from the contractor's outstandings for the period exceeded by him beyond the time fixed and until the work is completed and handed over.

18. In all matters of dispute of any kind not specially provided for in the agreement or of rates, penalties, measurements, quality of work, etc., the decision of the Chief or the Superintending Engineer, shall be final and legally binding.

19. No claims for damages for delays caused by officers of the department in the execution of the work will be considered, whatever may be the reasons for such delays. Contractors should bear this in mind when tendering for the work. Extension of time due to delays caused by the departmental officers will however be considered on the merits of each case.

20. The contract should not be sub-let.

21. All materials, tools and plant and machinery, that will be supplied by the Executive Engineer in the interest of the work shall be accepted by the tenderer at the rates fixed by the Executive Engineer. The tenderer will pay the hire on tools and plant and machinery as per rules from the date of taking over of such machinery, tools and plant from the Stores to the date

of return thereto, the dates considered being the dates of acknowledgments of the vouchers in each transaction.

22. The contractor should arrange for the payment of royalty and tolls.

Note.—(A) The contractor should at his own cost :—

(1) Provide rods, stakes, ropes and labour required in setting out the works.
(2) Provide all necessary scaffolding, centering labour and appliances for hoisting.
(3) Provide mortar mills, and sheds to keep materials under cover and also for workmen.
(4) Arrange for protecting work during inclement weather.
(5) Supply requisite temporary lights, water cisterns, water pumps and hoses, sieves, parahs, shoring, strutting and other requisite protective appliances during the progress of the work.
(6) Supply all water required for work and workmen and shall provide temporary latrines, and drains.
(7) Clean away all dirt, rubbish, superfluous materials and debris as they accumulate.
(8) Provide arrangements for pumping and baling of water from excavations and foundations wherever and whenever necessary with his own pumping apparatus, including necessary leading drains, slump pits, etc.
(9) Afford facilities to any other parties employed upon the work by the P. W. D. so that their work may proceed during the progress of the contract, and give such persons the use of ordinary scaffolding and ladders.
(10) The contractor is responsible for all accidents to workmen, etc., on the work and he must take precaution against all risk of accidents and if necessary provide for the same by Insurance at the proper time.

Note.—(B) It is the business of the contractor to make his own arrangements for quarries and supplies of materials.

Abstract estimate for Restoring Dadamudike Gundakalkere (Minor Tank) Nagamangala Taluk.

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		Rs.
	Bund to R. L. 51·00.				
1	Clearing jungle with roots, etc.	Grade	2 0 0	13	26
2	Earthwork cutting steps and grips	,,	3 0 0	10	30
3	Earthwork to bund gravel mixed with consolidation complete	C.yd.	0 6 0	2,772	1,040
3(a)	Earthwork to bund with watering and tamping (consolidation, etc., complete including carting charges	,,	0 3 0	4,840	908
4	Rough stone rivetment with jelly backing wedging, etc.	,,	1 8 0	1,387	2,081
5	Gravel backing to rivetment	,,	0 6 0	462	173
6	Turfing the slopes with watering, etc. ..	Syd.	0 1 0	2,542	159
	II. Breach work.				
1	Clearing sand and silt in breach	C.yd.	0 2 0	622	78
2	Earthwork excavation for foundation of puddle wall and using the same for bund in rear including consolidation	,,	0 4 0	488	122
3	Puddle work to breach portion of bund with $\frac{1}{6}$ gravel with watering and consolidation, etc., complete	,,	0 10 0	1,144	715
4	Grade stones including cutting figures and painting and fixing in concrete	Each	2 0 0	14	28
5	Index stones do	,,	0 8 0	14	7
6	Gauge stone cutting figures and painting, etc., complete do	,,	15 0 0	1	15
7	Register and date stone do	,,	3 0 0	1	3
8	B. M. stone cutting figure and painting do ..	,,	2 8 0	2	5

No.	Items of work	Unit	Rate	Quantity	Cost
	III. Sluice.		Rs. a. p.		Rs.
1	Earthwork excavation cut opening the bund and refilling with consolidation, etc. ..	C.yd.	0 3 6	151	33
2	(*a*) Burnt stone jelly concrete in surki mortar for foundation (1½ lime : 1 surki : 2 sand) ..	C.ft.	0 4 0	152	38
	(*b*) Do do cement concrete 1: 5 : 10	,,	0 6 0	152	57
3	Providing and fixing cast iron pipe 8″ diameter of Bhadravati including lead, etc., complete	R.ft.	3 0 0	36	108
4	(*a*) Size stone in surki mortar (1½ lime : 1 surki : 2 sand)	C.ft.	0 5 0	228	71
	(*b*) Do do in cement mortar 1 : 6	,,	0 6 6	228	93
5	Rough stone flooring, etc.	C.yd.	1 8 0	23	35
6	(*a*) Plastering with surki mortar and cement rendering	Sqr.	3 8 0	3·00	10
	(*b*) Pointing with cement mortar 1 : 3 ..	,,	3 8 0	3·00	10
7	(*a*) Burnt stone slabs 6″ thick dressed and fixed in surki mortar	S.ft.	0 7 6	150	70
	(*b*) Do do in cement mortar 1 : 6	,,	0 9 6	150	89
8	Cutting holes in guide orifice lower and upper orifices	No.	1 8 0	5	8
9	Providing Teakwood plug and rod	L. S.	..	..	25
10	Marking gauge on the gibbet slab pillars with cement plaster and cutting the figures in the same and painting with White lead and Japan	L. S.	..	..	10
	IV. Constructing Waste Weir at R.L. 48·00 in the left Waste Weir 70′ long.				
1	Earthwork excavation	C.yd.	0 2 6	517	81
2	(*a*) Laying burnt stone jelly concrete in surki mortar (1½ lime : 1 surki : 2 sand) ..	C.ft.	0 4 0	165	41
	(*b*) Do in cement mortar 1 : 5 : 10 ..	,,	0 6 0	165	62
3	(*a*) Size stone in surki mortar (1½ lime : 1 surki : 2 sand)	,,	0 5 0	146	46
	(*b*) Do do in cement mortar 1 : 6	C.ft.,	0 6 6	146	59
4	Cement concrete slab 6″ thick for coping 1 : 4 : 8	C.ft.	0 10 0	25	25
5	(*a*) Plastering with surki mortar	Sqr.	3 8 0	228	8
	(*b*) Pointing with cement mortar 1 : 3 ..	,,	3 8 0	228	8
6	Rough stone work with jelly wedging ..	C.yd.	1 8 0	31	47
	V. Constructing Right Waste Weir 300 feet long at R.L. 48·00.				
1	Earthwork excavation	C.yd.	0 2 6	4,323	675
2	(*a*) Burnt laying stone jelly concrete in surki mortar (1½ lime : 1 surki : 2 sand) ..	C.ft.	0 4 0	596	149
	(*b*) Do in cement mortar 1 : 5 : 10	,,	0 6 0	596	223
3	(*a*) Size stone in surki mortar 1½ lime : 1 surki, 2 sand)	C.ft.	0 5 0	326	102
	(*b*) Do do in cement mortar 1 : 6	,,	0 6 6	326	132
4	(*a*) Plastering with surki mortar	Sqr.	3 8 0	6.88	24
	(*b*) Pointing with cement mortar 1 : 4 ..	,,	3 8 0	6.88	24
5	Rough stone work with jelly backing and wedging including lead, etc.	C.yd.	1 8 0	112	168
6	Cement concrete slab 6″ thick for coping 1 : 4 : 8	C.ft.	0 10 0	89	56
	Inspection shed lumpsum (to be paid at rates fixed by the Executive Engineer)	..	..	..	200

Note.—Masonry will be constructed either in surki mortar or cement mortar and hence native rates are called for.

B. KRISHNA RAO,
Executive Engineer.